27, 2nd Main Road, Newry Sanctum, Thirumalai vasan Nagar, Thirumullaivoyal, Ch- 600062.
Email : geoconstructions.official@gmail.com **Mobile No:** +91 7200536592

STANDARD SPECIFICATIONS @ RS.2499/Sq.ft

Best Offer:

1 lakh valuable Modular kitchen setup + 50000rs valuable tv unit

OR

Rs 1,50,000

DESIGN:

- 2D Floor Plan
- Basic Elevation plan
- Isometric view plan

STRUCTURE:

- Basement height: Upto 3 feet
- Steel: Isteel, ARS (or) equivalent brand
- Aggregates: 20mm & 40mm
- Bricks: 9 inch for Exterior Wall & 4.5 inch for Interior Wall (Wire cut redbrick)
- Cement:
  Roof work - coromandel,
  ultra tech using M - sand
  Other works - Dalmia
  coromandal (or) equivalent
  brand)
- M Sand: Brickwork & P Sand: Plastering
- RCC Design Mix: M20
- Waterproofing: Dr.Fixit
- CeilingHeight:10Feet

KITCHEN:

- Ceramic Wall Tiles 2 Feet Above Kitchen Slab Upto RS.50/Sq.ft
- Kitchen Sink Faucet Upto 1500 Rs & ISI Marked
- Kitchen Sink: Stainless Steel Upto 2500 Rs
- Kitchen Granite Slab: 20 mm Thick Up to RS.140/ Sq.ft

BATHROOM: (Per Floor 2 Bathrooms only)

- Wall Tiles For 10 Feet Upto RS.45/ Sq.ft
- Sanitary Ware & CP Fitting Upto Rs 15,000
- CPVC/PVC: finolex , Asirvad (or) equivalent brand
- One Bathroom Accessories: EWC, Health Faucet, 2 in 1 Wall Mixer, OverheadShower- 1nos.
- Another One Bathroom Accessories: Indian closet with 2taps only- 1nos.
- Pvc heavy door only.

PLUMBING POINTS:

- **Bathroom –** 1 shower with wall mixer for hot & cold water, 1 floor mountwestern closet with health faucet.
  (All bathroom fittings are white color & basic model in jaqur essco, RAK)
- **Dining –** 1 wash basin with tap
- **Kitchen –** stainless steel sink with 1 tap. 1 RO point
- **Service –** 1 tap point & water outlet point for washing machine

DOORS & WINDOWS:

- Main Door: 1st quality mexin steel door ,French window with frame
- Internal Door: design Door Along With 2nd quality Teak Wood Frame
- Windows: Standard UPVC Sliding 2 Track window with mesh
- Providing and fixing MS grill for windows and ventilators

Door sizes:

- Main Door – 3.5′(Width) X 7′(Height)
- Rooms – 3′(Width) X 7′(Height)
- Bathroom & Balcony – 2.5′(Width) X 7′(Height)
- Window size – 3′(Width) X 4′(Height) (1 window per room)

PAINTING:

- Interior: Asian or JK Putty with Royal Emulsion
- Exterior: Asian Primer with Ultima Emulsion
- Ceiling putty including

FLOORING:

- Living & Dining Flooring: Tiles Up to 65 Rs Per Sq.ft (4x 2 tile size)
- Room & Kitchen Flooring: Tiles Up to 65 Rs Per Sq.ft
- Balcony & Open Area Flooring: Tiles Up to 45 Rs Per Sq.ft
- Staircase Flooring: Anti-skid Tiles Up to 45 Rs Per Sq.ft
- Parking Tiles: Anti-skid Tiles Up to 45 Rs Per Sq.ft

ELECTRICAL:

- Wires – Havells , Polycab (or) equilant brands
- Switches – havells , Legrand (or) equilant brands

.

Electrical Points

- **Bedroom** – 1 switch box with switches for 1 fan, 2 lights and 1 five amps socket with switch near door and 1 AC point
- **Bathroom-** 1 switch box with 1 switch for light and 1 switch for heater near thedoor & 15 amps socket for heater. 1 switch box with 1 five amps socket for hairdryer near the mirror
- **Hall-** 1 switch box near the door for 2 fans, 2 lights & 1 five amps socket andanother switch box with same set of switches near sofa. 1 switch box with 2 five amps sockets and switches along with cable point for TV connection
- **Dining-**1 switch box with switches for 1 fan & 1 light
- **Pooja-** 1 switch box with switch for 1 light
- **Kitchen-** 1 switch box with switch for 2 lights, 1 exhaust fan. 1 switch pointfor chimney. 1 switch box with 15 amps socket & switch for refrigerator. 1 switch box with two 15 amps socket & switch for mixi/ oven.
- **Service-**1 switch for light, 1 switch box with 15 amps socket & switch forwashing machine
- **Extras –** One 5 amps switch & socket for computer

COMPLEMENTRY SERVICES:

1. Overhead Tank: 1500 litters (Asirvad)
2. SS Staircase Railing
3. Parapet Wall 3 Feet Height
4. Soak pit (5 well rings)
5. Sill concrete used by needed area
6. Fiber mesh using all column and beam Joints
7. Basement filling time using pest control

TERMS & CONDITIONS: (Scope of the owner)

1. Water & Electricity to be arranged by the owner.
2. All the other works not mentioned in this agreement will be charged extra.
3. Time taken for completion of project is subject to availability of materials anddelays Due to natural climates.
4. Quotation valid up to 30 days.
5. Pile foundation or excavation in hard rock soil/water logging soil will becharged additionally.